



MPEC
NOWY SACZ

Tabela temperatur dla ogrzewania pompowego 120/65 °C
strefa klimatyczna III : - 20 °C

Temperatura zewnętrzna (°C)	Temperatura zasilania (°C)	Temperatura powrotu (°C)	Tz - Tp
-20	120	65	55
-19	118	64	54,0
-18	115	63	52,0
-17	112	62	50,0
-16	109	61	48,0
-15	107	60	47,0
-14	105	59	46,0
-13	103	58	45,0
-12	101	57	44,0
-11	99	56	43,0
-10	96	55	41,0
-9	94	54	40,0
-8	92	53	39,0
-7	90	52	38,0
-6	89	51	38,0
-5	88	50	38,0
-4	86	49	37,0
-3	84	48	36,0
-2	82	47	35,0
-1	78	46	32,0
0	75	45	30,0
1	72	44	28,0
2	69	43	26,0
3	66	42	24,0
4	65	41	24,0
5	64	40	24,0
6	63	40	23,0
7	62	40	22,0
8	62	40	22,0
9	62	40	22,0
10	62	40	22,0
11	62	40	22,0
12	62	40	22,0

14.03.2024 r.

KIEROWNIK
Dział Eksploatacji
Karolina Kita
Karolina Kita

DYREKTOR
ds. Inwestycji i Rozwoju
Stawomir Dudek
Stawomir Dudek